

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Dickinson  
 (County)  
Sagola Twp.

Located In:

Corner Code #

1. Public Land Survey

T 42N R 30W

L-3

T \_\_\_ R \_\_\_

K-4

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
 in Section

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
 Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

**MAR 24 2000**

**RECORDED**

1999 NOV 29 AM 10:31

REGISTERED DEEDS  
 DICKINSON COUNTY  
 REGISTERED DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_ **SECTION** \_\_\_\_\_

I, Robert F. Perkins, in a field survey on Sept. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-3 1/4 Corner 12  
 John Burt, D.S. 1850  
 Set 1/4 Post  
 Original Bearing Trees  
 Spruce 10" N68°E 38 Lks.  
 Spruce 16" S54°W 47 Lks.

K-4 1/4 Corner 11/12  
 John Burt, D.S. 1850  
 Set Spruce 1/4 Post  
 Tamarack 12" S77°E 8 Lks.  
 Cedar 16" N81°W 6 Lks.

ACCEPTED BY THE DICKINSON COUNTY  
 SURVEY PEER GROUP AS THE OFFICIAL  
 CORNER UNDER MICHIGAN PUBLIC ACT  
 363 OF 1990 AT A MEETING HELD ON  
11-13-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 No Evidence of Original Corner  
 or Accessories Found.  
 Established Corner Location by  
 Single Proportionate Method  
 from Section Corner 1/4 Mile East  
 and 1/4 Mile West.

K-4 No Evidence of Original Corner  
 or Accessories Found.  
 Found K.C. Corp. Pipe Marker with Brass  
 Cap as established by Neal Sperhake, RLS  
 on 6-2-1962. from G.L.O. Bearing Tree.  
 1960 Bearing Trees  
 Cedar 6" S78°E 30 Lks.  
 Cedar 6" N76°W 65 Lks.  
 Old Report #450

R.F. Perkins

COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 Set 3 1/2" Stamped Cap D.C. Remon. Marker  
 New Witnesses  
 Fir 4" N27°W(M.B.) 21.44' Nail/Tag  
 Fir 7" N65°E(M.B.) 58.35' Nail/Tag  
 Fir 12" S20°E(M.B.) 16.95' Nail/Tag  
 Spruce 14" S45°W(M.B.) 26.06' Nail/Tag  
 Placed carsonite Marker 1.0' North

K-4 Accepted Marker described in "B" above.  
 New Witnesses  
 Cedar 8" N15°W(M.B.) 20.81' Nail/Tag  
 Cedar 8" N20°E(M.B.) 14.20' Nail/Tag  
 Cedar 5" S55°W(M.B.) 16.35' Nail/Tag  
 Cedar 10" S75°E(M.B.) 19.55' Nail/Tag  
 Placed Carsonite Marker 1.0' South

Signed by Robert F. Perkins

Date Nov. 5, 1999

Surveyor's Michigan License No. 12027