

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County)		
West Branch Township		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 25 T 43N R 27W	10
	S 25 T 43N R 27W	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Jeremy J. Pipp, in a field survey on 8/21/2012AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (10) South One-Sixteenth corner common to Sections 25 and 26. Not set in original survey, no evidence of subsequent establishment.
- (11) Southwest One-Sixteenth corner of Section 25. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (10) Corner position established mid-point and on-line between the West One-Quarter corner and the Southwest corner of Section 25.
- (11) Corner position established at the intersection of the South and West One-Sixteenth lines of Section 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (10) DNR monument | (11) DNR monument |
| 4" Tamarack N59E 37.30' (1/16S,BT) | 6" Spruce N40E 92.62' (1/16S,BT) |
| 5" Cherry S60E 43.33' (1/16S,BT) | 14" Spruce S37E 121.34' (1/16S,BT) |
| 4" Spruce S67W 44.55' (1/16S,BT) | 19" Spruce S56W 87.89' (1/16S,BT) |
| 22" Tw. Maple N23W 31.97' (1/16S,BT) | 5" Spruce N25W 124.04' (1/16S,BT) |
| All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic. | All trees are blazed, scribed, and painted. Measurements are to nail in bearings are magnetic. |

Signed by Jeremy J. Pipp August 29, 2012
 Surveyor's Michigan License No. 50447

