

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

for corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County)		
<b>WEST BRANCH TOWNSHIP</b>		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling Section	S <u>19</u> T <u>43N</u> R <u>27W</u>	<u>10</u>
	S <u>19</u> T <u>43N</u> R <u>27W</u>	<u>15</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

\_\_\_\_\_ 6/11/2013AD  
 , Jeremy J. Pipp , in a field survey on 6/11/2013AD do hereby state  
 that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(10) South One-Sixteenth corner common to Sections 19 and 24. Not set in original survey, no evidence of subsequent establishment.

(15) West One-Sixteenth corner common to Sections 19 and 30. Not set in original survey, no evidence of subsequent establishment.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(10) Corner position established mid-point and on-line between the West One-Quarter corner and the Southwest corner of Section 19.

(15) Corner position established proportionate measurement and on-line between the South One-Quarter corner and the Southwest corner of Section 19.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(09) DNR monument  
 9" Cedar N45E 13.13' (1/16S,BT)  
 10" Cedar S63E 4.03' (1/16S,BT)  
 7" Cedar S25W 9.94' (1/16S,BT)  
 10" Cedar N61W 3.56' (1/16S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

(15) DNR monument  
 9" Spruce N37E 32.13' (1/16S,BT)  
 9" Poplar S68E 18.28' (1/16S,BT)  
 9" Poplar S51W 20.96' (1/16S,BT)  
 8" Cherry N44W 12.49' (1/16S,BT)

All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic.

Signed by \_\_\_\_\_  
 Surveyor's Michigan License No. 50447

Date August 08, 2013

For the Michigan Department of Natural Resources, Forest Resources Division



Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													