

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
WEST BRANCH TOWNSHIP	T 43N R 27W	G02
1. Public Land Survey	T 43N R 27W	G04
	T _____ R _____	_____
2. Property Controlling Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	●	3	2	1						
3													
4	7	8	9	●	10	11	12						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

\_\_\_\_\_ 6/25/2013AD  
 , Jeremy J. Pipp , in a field survey on 6/25/2013AD do hereby state  
 that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
 above were in conformance with regulations and rules therefore as required in the current manual of survey  
 instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
 a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
 the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
 re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G02) Quarter corner common to Sections 3 and 4. 1850: John Burt, DS. Set Quarter Section post witnessed by Spruce 8 N59E 25 links (16.50'), Cedar 12 N59W 9 links (5.94').

(G04) Quarter corner common to Sections 9 and 10. 1850: John Burt, DS. Set Quarter Section post witnessed by Cedar 12 S34W 3 links (1.98'), Cedar 12 N15E 18 links (11.88').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G02) No evidence of original survey. Corner position reestablished by single proportionate measurement between the Northwest corner and the Southwest corner of Section 10. Position is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

(G04) No evidence of original survey. Corner position reestablished by single proportionate measurement between the Northwest corner and the Southwest corner of Section 10. Position is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G02)	DNR monument	(G04)	DNR monument
5" B. Spruce	N54E 5.45' (1/4S,NBT)	10" Spruce	N21E 36.87' (1/4S,NBT)
6" B. Spruce	S31E 3.68' (1/4S,NBT)	5" Balsam	S63E 17.01' (1/4S,NBT)
6" B. Spruce	S58W 7.96' (1/4S,NBT)	6" Spruce	S03E 43.25' (1/4S,NBT)
5" B. Spruce	N40W 4.86' (1/4S,NBT)	6" Spruce	S69W 18.22' (1/4S,NBT)

All trees are blazed, scribed, painted, and signed. Measurements are to nail in side of tree, bearings are magnetic. A carsonite rail was set North 1.5 feet.

Signed by Jeremy J. Pipp Date August 08, 2013  
 Surveyor's Michigan License No. 50447

