

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

for corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County)		
WEST BRANCH TOWNSHIP		
1. Public Land Survey	T 43N R 27W	G03
	T 43N R 27W	B11
	T _____ R _____	_____
2. Property Controlling Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

5/09/2013AD

, Jeremy J. Pipp, in a field survey on 6/10/2013AD do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3							●						
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11	●												
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(G03) Section corner common to Sections 3, 4, 9, and 10. 1850: John Burt, DS. Set Cedar post witnessed by: Cedar 14 N15E 22 links (14.52'), Cedar 12 N59W 9 links (5.94'); 1958: Michigan DNR (Henry Peterson PS#8893) Set 1" Pipe with 4" Brass cap witnessed by Black Spruce 6 S89E 28 1/2 links (18.81'), Tamarack 7 N22W 25 links (16.50').

(B11) Quarter Corner common to Sections 30 and 31. 1850: John Burt, DS. Set Cedar post witnessed by: Hemlock 18 S38E 38 links (25.08'); Hemlock 14 N47W 30 links (19.80'). 1985: Michigan DNR (David Babbitt PS# 21558) Set 1" Pipe with 4" Aluminum cap witnessed by 40" W. Pine Stump S15E 74.3', 7" Black Cherry N58E 96.0', 3" B. Cherry in clump S51E 26.0', 3" Aspen not blazed N35W 18.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G03) Accepted found MDNR Monument and Four existing Witnesses (Two OBT's are mounds in proper position, Two NBT's: NW standing dead, SE dead & down). Position is accepted as a careful and faithful PERPETUATION of the position of the original corner.

(B11) Accepted found MDNR Monument and Three existing Witnesses (Two living NBT's: NE & SE Black Cherry; NBT Stump SE). Position is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G03)	DNR monument	(B11)	DNR monument
8" B. Spruce	N02E 25.38' (S3,NBT)	7" Cherry	N25E 24.42' (1/4S,NBT)
7" Tamarack	S65E 15.92' (S10,NBT)	7" Cherry	S58E 25.95' (1/4S,NBT)
7" Tamarack	S51W 13.26' (S9,NBT)	4" Maple	N88W 27.97' (1/4S,NBT)
8" B. Spruce	N51W 20.94' (S4,NBT)	10" Balm	N56W 10.6' (1/4S,NBT)
All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic. A Carsonite rail was set North 1.5 feet.		All trees are blazed, scribed, painted, and scribed. Measurements are to nail in side of tree, bearings are magnetic. A Carsonite rail was set North 1.5 feet.	

Signed by Jeremy J. Pipp  
 Surveyor's Michigan License No. 50447



Date August 08, 2013

For the Michigan Department of Natural Resources, Forest Resource Division

20214

20217