

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1999 NOV 29 AM 10:31

For corners in

Dickinson
 (County)
 West Branch Twp.
 1. Public Land Survey

Located in:

Corner Code #

T 43N R 27W
 T ___ R ___
 T ___ R ___
 T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___

E-11
 D-11

SURVEY &
 RE-MONUMENTATION

MAR 24 2000

REGISTER OF DEEDS
 DICKINSON COUNTY
 200 N. W. 1/4 Sec. 36, T. 43 N., R. 27 W., S. 24

Register of Deeds Stamp & File Number

SECTION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert F. Perkins, in a field survey on Aug. 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	19		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-11 Section Corner 28-29-32-33
 John Burt, D.S. 1850
 Original Bearing Trees
 Cedar 16" S42°E 25 Lks.
 Cedar 16" N73°E 12 Lks.

D-11 $\frac{1}{4}$ Corner 29
 32
 John Burt, D.S. 1850
 Original Bearing Trees
 Hemlock 12" S57°E 25 Lks.
 Cedar 18" N53°W 28 Lks.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PLAT GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-23-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11 Corner Re-established 6-27-86 by D.B. Babbitt, RLS #21558. See L.C.R.C. Liber 1, P. 404. Corner Witnessed 7-21-98 prior to Reconstruction of County Road 426 and Corner subsequently destroyed.

D-11 Corner Re-established 6-27-86 by D.B. Babbitt, RLS #21558. See L.C.R.C. Liber 1, P. 404. Corner Witnessed 7-21-98 prior to Reconstruction of County Road 426 and Corner subsequently destroyed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11 Corner Remonumented 8-6-99 from witnesses described in "B" above. Set 3 1/2" Stamped D.C. Remon. Corner 17.5' North of Road C/L in Rd. Shoulder. Set 3 1/2" Stamped D.C. Remon. W.C. with Carsonite Marker 33.0' North. Witnesses:
 Cedar 12" N45°W(M.B.) 48.38' (1986 B.T. Fd.)
 Cedar 10" N28°E(M.B.) 42.35' " "
 Cedar 10" S27°E(M.B.) 79.58' " "
 Cedar 8" S20°E(M.B.) 83.10' " "

D-11 Corner Re-monumented 8-6-99 from Witnesses described in "B" above. Set 3 1/2" Stamped D.C. Remon. Corner in Monument Box 8.8' North of Rd. C/L. Witnesses:
 Maple 10" N55°W(M.B.) 62.56' Nail/Tag
 Spruce 10" N08°W 27.00' (1986 B.T Fd)
 Spruce 14" S31°E 66.90' " "
 Spruce 8" S30°W 57.34' " "
 Placed Carsonite Marker 24' North

Signed by Robert F. Perkins
 Surveyor's Michigan License No. 12027

Date Nov. 5, 1999

