

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>43N</u> R <u>27W</u>	<u>H-13.</u>
	T <u>43N</u> R <u>27W</u>	<u>1-13.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, David B. Babbitt, in a field survey on 5/27/86, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13. South 1/4 corner of Section 34.
 Wood Post.
 Sugar 16" - N41E - 25 Lks.
 Lynn 16" - S54W - 15 Lks.

I-13. SE section corner of Section 34.
 Cedar 15" for section corner.
 Lynn 20" - N45E - 15 Lks.
 Cedar 12" - S45E - 17 Lks.
 Cedar 14" - S66W - 37 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13. Set MPOL between the SE and SW section corners of Section 34.

I-13. Set in site of large cedar the trunk of which lies northwesterly from site. Cedar turnout in place for sw OBT. Both cedars are very badly burned and all iron marks are gone. Calls for descend hill 1.00 ch. and foot of hill and enter swp. at 5.00 chs. fit well. Mea. south to found pipe for 1/4 cor. between Sections 2 & 3 is 2655'. Mea. east to twp. cor. is 10,554' and mea. west to sec. cor. common to secs. 32-33-4 & 5 is 10,568.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13. DNR monument.
 4" sugar maple N83W - 12.85'
 9" lynn N46E - 19.9'
 3" sugar maple S64E - 15.4'
 3" sugar maple S12W - 19.25'

I-13. DNR monument.
 4" y. birch S47E - 9.9'
 6" y. birch S7W - 24.7'
 8" basswood N53W - 7.5'
 6" h.maple N46E - 18.1'

Signed by

David B. Babbitt

Date

6-9-86

Surveyor's Michigan License No.

21558