

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Dickinson</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>27W</u>	<u>P-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>33</u> T <u>43N</u> R <u>27W</u>	<u>12, 13</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**Register of Deeds Stamp & File Number**

I, David Babbitt, in a field survey on March 13, 1986, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- F-12** Center 1/4 Corner of Section 33 not previously established
- 12** South 1/16 of Section 33 not previously established
- 13** South East 1/16 Corner of Section 33 (Center of the S.E. 1/4) not previously established

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- F12** Set at the intersection of the N-S and E-W 1/4 lines of section 33 by closed traverse.
- 12** Set M.P.O.L between the S. 1/4 corner and the center of section 33 by closed traverse.
- 13** Set at the computed center of the S.E. 1/4 of section 33 by closed traverse.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |                           |                            |
|---------------------------|----------------------------|
| <b>F12</b> (DNR Monument) | <b>13</b> (DNR Monument)   |
| 12" Cedar N27W 8.15'      | 8" Cedar S40W 18.15'       |
| 10" Cedar N58E 20.05'     | 7" Black Spruce S82E 13.4' |
| 9" Cedar S6E 22.15'       | 4" Cedar N48E 6.1'         |
| 7" Cedar S16W 26.7'       | 10" Cedar N4W 9.35'        |
- 
- |                           |
|---------------------------|
| <b>12</b> (DNR Monument)  |
| 6" Red Maple N40E 2.3'    |
| 8" Red Maple N77E 16.45'  |
| 4" Hard Maple S56E 24.55' |
| 7" Red Maple S58W 26.00'  |

Signed by David B. Babbitt Date 6-9-86  
 Surveyor's Michigan License No. 21558

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													