

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	<u>DICKINSON COUNTY</u> LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> ^{N.} X. , R. <u>27</u> ^{X.} W.	<u>G-5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 17, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Section Corner 9, 10, 15, & 16, T43N, R27W
1" iron pipe with 4" aluminum cap set by B. D. Buckler, R.L.S. on 10-29-1963.

Buckler's NBT's: Elm 14 N33°W 23 lks. "S9, NBT"
 Elm 10 N51°E 23 lks. "S10, NBT"

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

It was reported to the undersigned that Buckler's NBT's had been cut down during logging operations, said report being confirmed by the undersigned on 7-17-1978. Monument still intact, but only stumps of NBT's remained. Monument placed by Buckler on 10-29-1963 at site of an old wood post, rotted and down, which he stated checked "good with corners in vicinity." He found no original evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 4" aluminum cap (Buckler)

Sugar Maple 10 S 3°E (mag.) 5.4 ft. "S15, NBT"
 Sugar Maple 6 S75°W (mag.) 29.8 ft. "S16, NBT"
 Basswood 10 N38°W (mag.) 24.1 ft. "S 9, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE March 25, 1975
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

