

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ⁴³ NR ²⁷ W

Dickinson

COUNTY

DESCRIPTION OF CORNER Section corner common to sections 2,3,10 and 11

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER Cedar 7" N 25 W 23 links, marked S 3 NBT

Cedar 7" S 35 E 35 1/2 links, marked S 11 NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from probable original tamarack bearing tree. Stump in place with no identifying marks. Distance checks 53 links East to creek as per Government notes. Wood post in place with very old " cruisers witness tree ". Other bearing tree would fall in winter road.

Corner was found by Pat Byers, Kimberly Clark Corp. Timber cruiser.

Corner was placed and witnessed on 28 November 1956 with J. Doyle Voice.

SURVEYORS SEAL

Henry S. Peterson
Henry S. Peterson

SIGNED _____
REGISTERED LAND SURVEYOR

DATE 12/6/56