

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43-44 N.R. 27 W


Dickinson COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 3, 4, 33, 34

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 5/14/61

WITNESSES TO CORNER....18" W. Spruce (S 3 NBT) S 32° E 01 1/2 Links



16" W. Pine (S 4 NBT) S 37° W 28 Links

10" W. Pine (S 34 NBT) N 85° E 28 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by single proportionate measurement. Section Corner 1 mile to East and 3 miles to West. Location seems to check fairly well with swamp edges to East, North and South. Several down Cedar in vicinity but in bad condition due to recent logging in this area.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE August 2, 1961  
REGISTERED LAND SURVEYOR

Billy D. Buckler