

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 NR 27 W

Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 27 and 28  
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap  
WITNESSES TO CORNER White birch 12" S 44 W 57 links  
White birch 8" N 70 E 20 links


DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from original white pine bearing tree in fair condition. Notch on "BT" face very plain. Found remains of hemlock stump at field note bearing and distance of other bearing tree. Have good corner 1/2 mile north at corner of sections 21, 22, 27 and 28.

Corner was found while cruising timber in this area with Clarence Ryberg.

Corner was placed and witnessed on 5 June 1956.

SURVEYORS SEAL



Henry S. Peterson

SIGNED \_\_\_\_\_ DATE 6/6/56  
REGISTERED LAND SURVEYOR