

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ⁴³ NR ^{27 W}

Dickinson COUNTY

DESCRIPTION OF CORNER Section corner common to sections 11,12,13 and 14

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER White spruce 5" S 64 E 28 links

White spruce 7" N 68 W 24 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from original white pine bearing tree in fair condition. "BT" face visible. Notch very plain. Scribe mark plain. Remains of cedar stump at record bearing and distance of other bearing tree. Found remains of stake in soil at point where corner fell.

Corner was found while cruising timber in this area with Norman Karsten.

Corner was placed and witnessed on 16 July 1956.

SURVEYORS SEAL

Henry S. Peterson

Henry S. Peterson

SIGNED REGISTERED LAND SURVEYOR

DATE 7/19/56