

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ⁴³ NR. ²⁷ W.

Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 13 and 14

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER Cedar 9" S 89 E 30 1/2 links

Cedar 11" S 89 W 28 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from original cedar bearing tree in poor condition. Found axe marks in remains of stump buried in moss. Found two old stake points in moss at point where corner fell.

Corner was found while cruising timber in this area with Norman Karsten.

Corner was placed and witnessed on 16 July 1956

SURVEYORS SEAL

Henry S. Peterson
Henry S. Peterson
SIGNED _____ DATE 7/19/56
REGISTERED LAND SURVEYOR