

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 NR. 27 W.

Dickinson

COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 8 and 9

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER Tamarack 4" N 39 E 13 links, marked 1/4 S NBT

Tamarack 5" S 11 E 8 links, marked 1/4 S NBT

Distances measured from center of brass cap to NBT notch.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one original tamarack bearing tree (16" S 81 E 25 links), down, in poor condition. Found description blaze and BT blaze overgrowth with notches plain. Found remains of original cedar bearing tree (14" N 37 W 33 links) in place with no identifying marks. Two old wood posts in place. Have good corner 1/2 mile north.

Corner found while cruising timber in this area.

Corner placed and witnessed on 23 September 1957 with Clarence R. Ryberg.

SURVEYORS SEAL



SIGNED

Henry S. Peterson
REGISTERED LAND SURVEYOR

DATE

9/25/57