

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T..43 NR..27W..

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER  $\frac{1}{4}$  corner between sections 12 and 13 -----

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap -----

WITNESSES TO CORNER White pine 10" S 75 E .61 links -----

Marked  $\frac{1}{4}$  S NBT -----

White pine 14" N 54 W .42 links -----

Marked  $\frac{1}{4}$  S NBT -----

Distances measured from NBT notch to center of brass cap.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from two probable original cedar bearing trees. Cedar approximate 8" S 31 E 15 links in place, down, with plain overgrowth scar of description blaze, axemarks plain. Remains of cedar 10" N 42 W 20 links in place with no identifying marks. Distance checks good  $\frac{1}{2}$  chain to west to swamp edge. Squared white pine near by for approximate corner. Wood post near by placed by Kimberly Clark cruisers.

Corner found while cruising timber in this area with Norman J. Karsten.

Corner placed and witnessed on 7 August 1958 with Norman J. Karsten.

SURVEYORS SEAL



SIGNED Henry S. Peterson  
REGISTERED LAND SURVEYOR

DATE 8/8/58