

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD ✓

T. 43N NR. 27W

Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 21 and 22

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap.

WITNESSES TO CORNER Black spruce 4" N 49 W 15 links, marked 1/4 S NBT

Black Spruce 5" S 20 W 11 links, marked 1/4 S NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original tamarack bearing tree (Tam 8 N 10 W 20) in good condition. Scribe marks plain. Other tamarack bearing tree in place in poor condition, with no identifying marks. (tam 12 S 70 E 35) Found remains of probable original stake point in water under moss. Old Tamarack stub scribed for approximate corner nearby.

Corner placed and witnessed 31 August 1960 with Toivo Kauma.

SURVEYORS SEAL


SIGNED Henry S. Peterson DATE 8-31-60
REGISTERED LAND SURVEYOR