

1. Public Land Survey T 43N R 27W B-11. C-12.  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling S 32 T 43N R 27W 2.  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**DICKINSON  
CO.**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 6/17, 26&27, 19 85, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

B-11. North 1/4 cor. of Section 31. Cedar post. Hemlock 18 - S38E 38 Lks.  
 Hemlock 14 - N47W 30 Lks.

C-12. West 1/4 cor. of Section 32. Cedar post. Cedar 16" S28<sup>0</sup>W 25 Lks.  
 Cedar 16" N17<sup>0</sup>E 37 Lks.

2. East 1/16 cor. on the North sec. line of Section 32. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11. Set by single proportion to the G.L.O. record between the NE and NW sec. cors. of Section 31.

C-12. Set D.N.R. Monument in front of 10" cedar signature tree beside stump and remains of very old squared up 12" tamarack. Signatures on tree H.F. Smith and Allen Smith dated 1925. It was the common practice of H.F. Smith to sign only where he saw good evidence of the original corner. No sign of original B.T.s found at this time. This cor. is in line with blazed lines south and west. A count of growth rings on the blazed trees indicates that they were blazed about 1925 presumably at the same time the signature tree was marked. Measurement north to old dry streambed fits well with the original survey record and measurements to other known corners in this Twp. fit well.

2. Set M.P.O.L. between the NE sec. cor. and the North 1/4 cor. of Section 32.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11. D.N.R. Monument Blaze on 40" w.p. stump S15<sup>0</sup>E 74.3'  
 7" Bl. Cherry N58<sup>0</sup>E 96.0'  
 3" Bl. Cherry in clump S51<sup>0</sup>E 26.0'  
 3" Aspen not blazed N35<sup>0</sup>W 18.6'

C-12. D.N.R. Monument 9" Cedar N53<sup>0</sup>E 35.9' 4" Cedar N73<sup>0</sup>W 32.2'  
 7" Cedar N9<sup>0</sup>W 28.9' 7" Cedar S49<sup>0</sup>W 23.0'  
 Face of 10" Cedar signature tree - N52<sup>0</sup>W 8.2'

2. D.N.R. Monument Spruce S21<sup>0</sup>W 77.65' 6" Aspen N26<sup>0</sup>E 23.9'  
 8" Bl. Cherry S16<sup>0</sup>E 98.2' (E blacktop road-south 12.5')  
 7" Apple N73<sup>0</sup>W 54.3'

Signed by David B. Babbitt Date 2-11-86

Surveyor's Michigan License No. RLS 21558