

1. Public Land Survey T 43N R 27W E-10 ✓
 T R
 T R
 T R
 2. Property Controlling S 28 T 43N R 27W 7 -
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

DICKINSON
Co.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 6/20 & 6/26, 19 85, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-10 East 1/4 corner of Section 29.
 Wood post. Spruce 10N 87°W 28 links.
 Cedar 8S 24°E 19 links.

7. North 1/16 cor. on the east sec. line of Section 28.
 Not previously est.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10 Set from found remains of stump of original cedar bearing tree showing marks of the lower (B.T.) blaze but no scribe marks visible at this time. Stump in very poor condition.

7. Set M.P.O.L. between the east 1/4 cor. and the NE sec. cor. of Section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10 6" B. Spruce S23°W 9.3' (DNR Monument)
 4" Balsam Fir N42°E 2.1'
 10" Tamarack N79°E 43.5'
 12" Tamarack S88°E 75.9'

7. 6" Cedar N56°W 47.8' (DNR Monument)
 4" Cedar N67°E 41.85'
 10" Cedar S44°E 26.8'
 7" Cedar S54°W 25.0'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by

David B. Babbitt

Date

2-11-86

Surveyor's Michigan License No. 21558