

1. Public Land Survey T 43N R 27W G-12 F-13 & G-13
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

DICKINSON
CO.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 4/29 & 11/13, 19 85, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-12. East 1/4 cor. of Section 33. Wood post. W. Pine 30 - N16W 15 Lks.
 DO 30 - S24E 40 Lks.

F-13. S 1/4 corner of Section 33. Cedar post. Cedar 8" - N66E 24 Lks.
 Cedar 5" - N44W 20 Lks.

G-13. Southeast sec. cor. of Section 33. Cedar post. Cedar 10 - N64E 29 Lks.
 Y.Birch 10 - N69W 17 Lks.
 Y.Birch 14 - S50E 49 Lks.
 Hemlock 14 - S55W 22 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12. Set from stump of SE original bearing tree stump. A 32" w. pine lower face with some scribing plain. The upper face had been cut off but some callouse growth shows below the cut.

F-13. Set M.P.O.L. between the SE and SW sec. cors. of Section 33. Several old cedar stumps in the area but could not identify any as O.B.T.'s.

G-13. Set by single proportion between the SW sec. cor. of Section 33 and the SE sec. cor. of Section 34. Remains of badly burned cedar in the area but could not identify any as an O.B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12. D.N.R. Monument. 5" twin R. Maple N72⁰E 18.7' 9" R. Maple S8⁰E 12.3'
 6" R. Maple S66⁰E 26.5' 10" W. Birch S64⁰W 47.4'

F-13. D.N.R. Monument 14" W. Spruce N50⁰E 63.90' 7" twin Black Spruce S45⁰W 37.70'
 8" Tamarack S46⁰E 62.50' 6" Cedar N60⁰W 6.35'

G-13. D.N.R. Monument 3" B. Spruce N14⁰E 26.65' 8" R. Maple S61⁰W 24.50'
 4" B. Spruce N85⁰E 18.00' 4" Balsam Fir N46⁰W 22.90'

Signed by

David B. Babbitt

Date

2-11-86

Surveyor's Michigan License No. RLS 21558