

1. Public Land Survey T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S 33 T 43N R 27W 16. 15. 7.
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

**DICKINSON
 Co.**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 11/13&14 & 6/20, 19 85, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

16. East 1/16 cor. on the south sec. line of Section 33. Not prev. est.
 15. West 1/16 cor. on the south section line of Section 33. Not prev. est.
 7. North 1/16 cor. on the east section line of Section 33. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

16. Set M.P.O.L. between the south 1/4 cor. and the SE sec. cor. of Section 33.
 15. Set M.P.O.L. between the south 1/4 cor. and the SW sec. cor. of Section 33.
 7. Set M.P.O.L. between the east 1/4 cor. and the NE sec. cor. of Section 33.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

16. D.N.R. Monument 6" R. Pine S32⁰E 58.8' 15" Spruce N1⁰E 45.9'
 7" R. Pine S14⁰W 53.8' 6" Spruce N61⁰E 7.0'
15. D.N.R. Monument 12" Cedar N12⁰E 23.8' 11" Cedar S30⁰E 23.7'
 10" Cedar N59⁰E 16.0' 10" Cedar N38⁰W 25.2'
7. D.N.R. Monument 5" Tamarack N40⁰W 84.1' 5" Balm of Gilead S8⁰E 21.4'
 8" W. Spruce N89⁰E 48.0' 4" Aspen N48⁰E 10.8'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by

David B. Babbitt

Date

2-11-86

Surveyor's Michigan License No. RSL21558