

1. Public Land Survey T 43N R 27W F-11, E-12, & G-11
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
 3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

**DICKINSON
CO.**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	9	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 4/12 & 6/20&27, 19 85, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- F-11. North 1/4 cor. of Section 33. Cedar post. Spruce 12 - S42E 24 Lks.
Tamarack 10 - N57W 28 Lks.
 - E-12. W 1/4 cor. of Section 33. Wood post. Cedar 18 S84⁰E 37 Lks.
Cedar 18 N70⁰W 18 Lks.
 - G-11. NE corner of Section 33. Wood post. Hemlock 14 S50E 21 Lks.
Hemlock 18 N36W 33 Lks.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- F-11. Set M.P.O.L. between the NE and NW sec. cors. of Section 33. O.B.T.'s probably destroyed by road const.
 - E-12. Set from stump of original witness: Cedar 18 S84⁰E 37 Lks. scribing and notch plain, stump in fair condition.
 - G-11. Found pipe, not of record, but is compatable for bearing and distance to all known cor. mons. in the area. I find no reason to question this location. Re-witnessed as found.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- F-11. D.N.R. Monument 10" Cedar N20⁰W 60.4' 6" Cedar S10⁰W 55.6'
6" Cedar S32⁰E 45.4' 11" Cedar N18⁰E 68.15'
 - E-12. D.N.R. Monument (in creek) 7" Cedar N7⁰W 47.5' 6" Cedar N83⁰E 30.9'
7" Cedar S74⁰W 24.8' 12" Cedar N86⁰E 10.6'
 - G-11. 1-1/2" O.D. pipe in place. 10" Sugar Maple S46⁰W 68.3' 10" Red Maple S81⁰W 48.0'
11" Red Maple N48⁰W 32.2' 9" Red Maple N86⁰E 22.2'

Signed by David B. Babbitt Date 2-11-86
 Surveyor's Michigan License No. RLS 21558