

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

 (County)

Located In:

Corner Code #

1. Public Land Survey	T <u>43N</u> R <u>27W</u>	<u>A6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>18</u> T <u>43N</u> R <u>27W</u>	<u>10</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 14 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(A6) Quarter corner common to Section 18, T43N-R27W and Section 13, T43N-R28W. Corner established by Austin Burt, Deputy Surveyor: "North...40.00 Set cedar post qr. section corner. Tamarac 10 S53W 47, Tamarac 6 N82E 28". Found no subsequent record.
 (10-Sec. 18) South 1/16 corner between Sections 18, T43N-R27W and 13, T43N-R28W. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A6) Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner on a line of mean true bearing, on the range line defined by monumented section corners 2648.00' northerly and southerly, being proportionate to the original record. At the position for the corner, I placed a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner, a partially downed hog-wire/barbed-wire N-S fence is 1' east.

(10-Sec. 18) Established the corner on the range line, on a line of mean true bearing between Quarter corner 1324.00' Northerly and Section Corner 1324.00' Southerly. At the position for the corner I placed a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A6) Set 1" pipe with 4" MDNR cap.	(10) Set 1" pipe with 4" MDNR cap.
Blazed and scribed the following:	Blazed and scribed the following:
12" Cedar N15E 35.8' "1/4S NBT"	5" Spruce N36E 52.7' "1/16S BT"
9" Tamarack S47E 8.5' do	3" Spruce S20E 11.8' do
10" Cedar S79W 23.9' do	7" Aspen S29W 21.1' do
16" Cedar N14W 19.4' do	7" Spruce N71W 38.6' do
Placed a squared cedar post adjacent.	Placed a squared cedar post adjacent.
Bearings are magnetic. Distances are to notch in lower blaze.	Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/7/00

For the Michigan Department of Natural Resources - Forest Management Division