

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>18</u> T <u>43N</u> R <u>27W</u>	<u>7</u>
	S <u>19</u> T <u>43N</u> R <u>27W</u>	<u>5</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 17 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5		4		3		2		1		
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (7-Sec. 18) North 1/16 corner between Sections 17-18. Corner not established in the original survey. Found no subsequent record.
 (5-Sec. 19) North 1/16 corner, Section 19. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 18) Established the corner on a line of mean true bearing between Section corner 1321.99' northerly and quarter corner 1321.99' southerly. At the position for the corner, I placed a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
 (5-Sec. 19) Established the corner on a straight line between Quarter corner 1324.07' northerly and Center of Section 1324.07' southerly. At the position for the corner I placed a 1" IDx32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 10" Cedar N59E 17.2' "1/16S BT" 9" Cedar S55E 16.6' do 10" Cedar S23W 41.2' do 10" Tamarack N45W 17.8' do Squared a 5" tam'k, scribed "1/16" N73W 1.9' to center. Bearings are magnetic. Distances to notch in lower blaze unless noted.	(5) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following: 6" Sugar N44E 10.5' "1/16S BT" 7" double Sugar S27E 2.9' do 8" Sugar S88W 25.9' do 8" Sugar N21W 23.0' do Placed squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
--	--



Signed by Stephan J. Szyszkoski Date 2/7/00
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division