

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>43N</u> R <u>27W</u>	<u>M5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jun 06 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (M5) Corner common to Sections 12-13 T43N-R27W and 7-18 T43N-R26W. Remonumented in the original position from two original tamarack BTs by Henry S. Peterson RLS in 1956. 1" pipe with 4" brass cap. 8.Spruce 6 N24W 33 links, Cedar 5 S71E 31 links, 8.Spruce 5 S51W 12 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(M5) Recovered the 1956 monument as described, in good condition, and at record bearing and distance from all three 1956 NBTs. The 8.Spruce NW is a decaying stump with portion of notch visible, the 8.Spruce SW is a dead stub with scribing plain, the Cedar is in good condition with overgrown blazes. No trace of the original Tam. bearing trees. Left the monument in place and made new witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(M5) Found 1" ID iron pipe with 4" brass MDOC cap. Blazed and scribed:  
 8" Cedar N85E 17.1' "S7 NBT"  
 10" Tam. S22E 17.3' "S18 NBT"  
 10" Tam. N62W 19.0' "S12 NBT"  
 Cedar S68E 21.1' (1956 NBT)  
 Sq'd cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 8/8/01

For the Michigan Department of Natural Resources - Forest Management Division