

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Dickinson</u>	Located In:	Corner Code #
(County)		
WEST BRANCH TOWNSHIP		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>25</u> T <u>43N</u> R <u>28W</u>	<u>11</u>
	S <u>25</u> T <u>43N</u> R <u>28W</u>	<u>13</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

, Jeremy J. Pipp, in a field survey on 6/18/2013AD
6/17/2013AD do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(11) Southwest One-Sixteenth corner of Section 25. Not set in original survey, no evidence of subsequent establishment.

(13) Southeast One-Sixteenth corner of Section 25. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11) Corner position established at the intersection of the South and West One-Sixteenth lines of Section 25. Monument falls +/-1 feet South of East-West fence line

(13) Corner position established at the intersection of the South and East One-Sixteenth lines of Section 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) DNR monument
9" J. Pine N27E 14.98' (1/16S,BT)
Fence Post N82E 11.46' (- , -)
12" J. Pine N56W 27.81' (1/16S,BT)
8" J. Pine N16W 14.60' (1/16S,NBT)
All trees are blazed, scribed, painted, and signed. Measurements are to nail in side of tree, bearings are magnetic.

(13) DNR monument
4" Ironwood N78E 30.57' (1/16S,BT)
5" Maple S43W 43.85' (1/16S,BT) N-E-S Fence cor. N18W 19.28' (- , -)
All trees are blazed, scribed, painted, and signed. Measurements are to nail in side of tree, bearings are magnetic.

Signed by Jeremy J. Pipp Date August 08, 2013
Surveyor's Michigan License No. 50447



For the Michigan Department of Natural Resources, Forest Resource Division

20229
20228