

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| <u>Dickinson</u> | Located In: | Corner Code # |
| (County) | | |
| WEST BRANCH TOWNSHIP | | |
| 1. Public Land Survey | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S 23 T 43N R 28W | 14 |
| | S 23 T 43N R 28W | 16 |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

, Jeremy J. Pipp, in a field survey on 6/11/2013AD do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (14) South One-Sixteenth corner common to Sections 23 and 24. Not set in original survey, no evidence of subsequent establishment.
- (16) East One-Sixteenth corner common to Sections 23 and 26. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (14) Corner position established mid-point and on-line between the East One-Quarter corner and the Southeast corner of Section 23.
- (16) Corner position established mid-point and on-line between the South One-Quarter corner and the Southeast corner of Section 23.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (14) DNR monument | (16) DNR monument |
| 9" Maple N12E 17.30' (1/16S,BT) | 3" Ironwood N36E 19.83' (1/16S,BT) |
| 4" Cherry S40E 37.86' (1/16S,BT) | 4" Spruce S43E 26.01' (1/16S,BT) |
| 6" Cherry S28W 12.63' (1/16S,BT) | 6" Poplar S57W 14.35' (1/16S,BT) |
| 8" Maple N59W 8.23' (1/16S,BT) | 6" Maple N32W 40.32' (1/16S,BT) |
| All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic. | Angle Iron N24E 22.6' All trees are blazed, scribed, and painted. Measurements are to nail in side of tree, bearings are magnetic. |

Signed by Jeremy Pipp Date August 08, 2013
 Surveyor's Michigan License No. 50447

For the Michigan Department of Natural Resources and Forest Resource Division

