

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1998 FEB 20 AM 9:40

For corners in

Dickinson
(County)

Located In: _____ Corner Code # _____

1. Felch Township
Public Land Survey
T 43N R 28W E-12
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling
in Section
S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous
Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REGISTERED DEEDS
DICKINSON COUNTY
RON MOUNTAIN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Edward Kazianka, in a field survey on January 8, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12 $\frac{1}{4}$ Corner between Sections 32 and 33.
Corner fell in Beaver Pond. Corner was not set. J. Burt, D.S. in September 1850.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12 Section corners $\frac{1}{2}$ mile north and south are in with a distance of 5318.12 feet between them. Set the Quarter Corner at the mid-point and on line between them.

ACCEPTED BY THE DICKINSON COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT
345 OF 1990 AT A MEETING HELD ON
2-19-98
ROP
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12 Set a 2 $\frac{1}{2}$ " Dickinson County Remon. cap on a 6 foot Alun. rod.
Spruce 8 N 05W 240.60 feet. P. Pole N44E 265.35 feet.
P. Pole S34E 79.77 feet. P. Pole S16W 343.40 feet.
1 $\frac{1}{2}$ " Iron pipe S11E 15.86 feet. Carsonite Marker N45W 2.0 feet



Bearings are magnetic.)
Signed by Edward Kazianka
Surveyor's Michigan License No. 14765

Date Feb. 20, 1998