

**SURVEY &
REMONUMENTATION**

MAR 03 1998

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1997 APR 18 PM 1:12

For corners in **SECTION**

<u>Dickinson</u> (County)	Located In:	Corner Code #
West Branch Township.		
1. Public Land Survey	T <u>43N</u> R <u>28W</u>	<u>I-11 & I-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
DICKINSON COUNTY
IRON MOUNTAIN, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Edward Kazianka, in a field survey on March 12, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11 Corner common to Sections 26, 27, 34 & 35.
Wood post set by J, Burt in September, 1850.
W. Pine 36 S29E 31 lks. W. Pine 30 N43W 29 lks.
Dept. of Conservation pipe and cap set by D. DeLaMater on August 27, 1952.
Aspen 8 N73E 27 lks. Aspen 8 S34W 29 lks.

I-12 Quarter Corner between Sections 34 & 35.
Wood post by J. Burt in September, 1850.
W. Ash 8 S88E 20 lks. B. Ash 10 N45W 26 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Dept. of Conservation monument.
1952 NBT's are gone. Remains of 36" Pine stump still present.

I-12 No evidence of original corner or accessories found.
Section corners 1/2 mile north and south are set with a distance of 5293.28 feet between them. Set Quarter Corner at the mid-point and on line between the two section corners.

ACCEPTED BY THE DICKINSON COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT
345 OF 1990 AT A MEETING HELD ON
4-15-97

RAP
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Dept. of Conservation monument.
Aspen 6 N37E 23.25 feet. Spruce 11 N88W 39.30 feet.
Spruce 4 N29W 6.30 " " 6 S30E 9.00 "
Carsonite stake set 3.0 feet North.

I-12 Set Dickinson County Survey cap on a six foot Alun. Rod.
Cedar 10 N03W 56.40 feet. Cedar 11 N88E 25.60 feet.
" 3 S50E 44.70 " " 7 S22W 23.38 "
Carsonite stake set 2.0 feet South.
Left bank of the Ford River is approximately 52 feet South.



Signed by Edward Kazianka Date April 16, 1997
Surveyor's Michigan License No. 14765