

SURVEY & REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

1997 APR 18 PM 1:12

For corners in **SECTION**

Dickinson

(County)

West Branch Township.

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>43N</u> R <u>28W</u> | <u>J-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

REGISTER OF DEEDS
 DICKINSON COUNTY
 RON MOUNTAIN MI 49801

Register of Deeds Stamp & File Number

I, Edward Kazianka, in a field survey on March 12, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11										●			
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- J-11 Quarter Corner between Sections 26 & 35.
 Wood post set by J. Burt in September, 1850
 Tamarack 10 S80E 04 lks. Spruce 8 N65W 33 lks.

 Dept. of Conservation pipe and cap set by W. Buckler on October 7, 1963.
 Cedar 5 N30E 16 lks. Cedar 8 N61W 35½ lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-11 Found a 3/8" Re-rod with the two Dept. of Conser. NBT's alive and standing.
 Could not find the corner monument. Set the Quarter Corner 35½ links from the northwest NBT and 16 links from the northeast NBT.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 4-15-97
R.O.P.
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-11 Set Dickinson County Survey cap on a six foot Alum. rod.
 Cedar 11 N64W 23.50 feet. Cedar 8 N34E 10.60 feet.
 " 7 S49E 5.62 " Spruce 6 S79W 2.35 "
 Carsonite stake set 2.0 feet South.



Signed by Edward Kazianka Date April 16, 1997

Surveyor's Michigan License No. 14765

FEB 26 1998