

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 43 NR 28 W

Dickinson COUNTY

DESCRIPTION OF CORNER Section corner common to sections 4,5,8 and 9
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap
WITNESSES TO CORNER Cedar 12" S 56 E 42 links
marked, T43N R28W S 9 NBT
Black spruce 7" N 9 E 1 1/2 links
Marked T43N R28W S4 NBT
Distances measured from center of brass cap to notch.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Corner was found by H. S. Peterson and N. J. Karsten, Foresters, Iron Mountain while
crossing timber in this area.

Corner was replaced from two original bearing trees. Found 1 tamarack bearing tree
in fair condition. Scribe marks plain. Found spruce stump in place with scar tissue
for other bearing tree. Stump in poor condition.

1956
Corner was placed on 22 October with Norman J. Karsten.

SURVEYORS SEAL

Henry S. Peterson

Henry S. Peterson

SIGNED REGISTERED LAND SURVEYOR

DATE 10/27/56