

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T42-43 NR. 28 W. . .

----- Dickinson -----

----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 5-6-31-32 -----
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----
WITNESSES TO CORNER 40" W. Pine stump N 65° E 59 links
"S 32 NBT" -----
8" Aspen S 75° W 12 links
"S 6 NBT" -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established section corner by double proportionate measure to corners one mile in all four directions.

Position fits swamp edges south and east.

Found no evidence of original corner.

Found post about 70 links south which was not accepted.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 9/5/57
REGISTERED LAND SURVEYOR -----