

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 NR 28-29 W.

----- Dickinson -----

----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 30-31-25-36 -----
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----
WITNESSES TO CORNER 7" Cedar S 54° E 21 links -----
"S 31 NBT" -----
8" Cedar N 5° W 7 links -----
"S 25 NBT" -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from one cedar B.T. in fair condition. Scribe marks obliterated, bearing N 15° E 42 links. Found tamarack stump bearing N 38° W 22 links.

Found blazed tree on ground at corner.

Distance checks 2.00 chs. north to swamp edge.

Corner lies in swamp.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 8/2/57
REGISTERED LAND SURVEYOR -----