

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD


Dickinson COUNTY
T 43N R 28-29W

DESCRIPTION OF CORNER 1/4 corner between Sections 7 and 12

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED January 28, 1969

WITNESSES TO CORNER..... Cedar 10 N65°E 37 lks. "1/4 S NBT"



Cedar 7 S56°W 21 lks. "1/4 S NBT"

Cedar 12 N44°W 29 lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at site of an old squared and scribed cedar post which had been re-witnessed about 50 years ago (by tree ring count) with a blazed and scribed cedar to the southeast. Too much snow to identify any original BT'S, although there are some down tamaracks and tamarack stumps, some with axe marks, close to the corner. Post is located 2.60 chains North of south bank of a small stream (record distance is 2.53 chains) and 118.90 chains South of an original township corner (record distance is 118.75 chains).

The party who set the found scribed post is unknown.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

10/20/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68