

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 43N R 28W

DESCRIPTION OF CORNER 1/4 corner between Sections 6 and 7

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 22, 1969

WITNESSES TO CORNER..... Cedar 5 N62 $\frac{1}{2}$ ⁰E 28 lks. "1/4S, NT"



Cedar 8 S47⁰E 25 lks. "1/4S, NT"

Cedar 6 S12⁰W 23 lks. "1/4S, NT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at site of an old scribed 3"x3"x5 $\frac{1}{2}$ ' cedar post, set many years ago (maybe as much as 50 years) by an unknown surveyor. Post had been re-witnessed with a Spruce 8 S17⁰W 14 links, now a rotted off stump bearing a notched vertical blade at the root crown, scribed "BT". Not a recorded original BT, however. Also found rotted remains of an elder post in the swamp post, possibly part of original post. Found no positive evidence of original corner post or its accessories, however. Several blazed cedars bearing cruisers' signatures face the corner.

Distance west to SW corner of Sec. 6 is 40.40 chains and east to SE corner of Sec. 6 is 40.12 chains, but this corner is slightly south of a point on a direct line between Section Corners.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

1/28/71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68