

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY  
T 43N R 28W

DESCRIPTION OF CORNER East 1/16 corner between Sections 6 and 7

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 23, 1969

WITNESSES TO CORNER..... W. Pine 15 S10 1/2° W 73 1/2 lks. "1/16S, BT"



W. Pine 16 S88 1/2° E 51 1/2 lks. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between 1/4 corner 20,077 chains west and section corner 20,077 chains east. Found no evidence that a corner had ever been established previously in this position, and found a dead 5" maple blazed on four sides bearing S 3 1/2° W 42 links from corner. Forester's paint line runs south from blazed tree.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR

DATE

11/28/71

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68