


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY  
T 43-44N R 28W

DESCRIPTION OF CORNER Section Corner 4, 5, 32, and 33  
CORNER MONUMENT 1" I. D. Iron pipe with 4" aluminum cap  
DATE MONUMENT PLACED AND WITNESSED September 30, 1969  
WITNESSES TO CORNER..... Sugar Maple 7 S43°E 99½ lks. "84, NBT"



Sugar Maple 6 N32½°E 50½ lks. "833, NBT"  
Sugar Maple 5 N30½°W 42½ lks. "832, NBT"  
AND  
Basewood 8 S80°W 76 lks. "85, NBT"

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument set on line between an original section corner 238.00 chains east and an original township corner 160.01 chains west. Corner not set proportionately, but at a point from which a line south between Sec. 4 & 5 to an original SE corner of Sec. 5 passes through the approximate center of a nest of three granitic boulders which are believed to be the same boulders mentioned in the original field notes for the line between Sec. 4 and 5. The boulders span an area about 70 links E & W by 25 links N & S, and although the distance from them to the corner is about two chains greater than the record, the total distance between the corner recorded here and the SE corner of Sec. 5 compares very closely with the record. (Record: 78.90 chains; measured: 78.89 chains).

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR

DATE

1/28/71

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68