

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 43N R 28W

DESCRIPTION OF CORNER 1/4 corner between Sections 5 and 6

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED October 3, 1969

WITNESSES TO CORNER..... Balm of Gilead 16 N36°W 31 lks. "1/4 S, NBT"



White Spruce 8 N9½°E 50 lks. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement on line between section corner 40.243 ch. south and section corner 38.935 ch. north. Corner is 20 lks. south of a stream 2 lks. wide course SW.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

Arthur O. Enger

DATE

February 1, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68