

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 43N R 28W

DESCRIPTION OF CORNER South 1/16 corner between Section 5 and 6

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED October 6, 1969

WITNESSES TO CORNER..... W. Spruce 5 N72¹/₂^oE 46¹/₂ lks. "1/16S, BT"



Cedar 14 N15^oW 115 lks. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established by proportionate measurement on line between section corner 20.121 ch. south and 1/4 corner 20.121 ch. north. Corner lies in a beaver pond. No evidence that the corner had been previously established.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE February 1, 1972

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68