

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 43N R 28W

DESCRIPTION OF CORNER 1/4 corner between Sections 5 and 8

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED September 22, 1969

WITNESSES TO CORNER..... Cedar 9 S59 $\frac{1}{2}$ ^oW 18 $\frac{1}{2}$ lks. "1/4S, NBT"



Cedar 11 S13 $\frac{1}{2}$ ^oE 20 $\frac{1}{2}$ lks. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found an 8" cedar N24^oW 29 lks. with a NE blaze marked "1/4 5/8"
and names "Slater, Samsyn 3-26-41" and "H. F. Smith, W. Bruce 9/26/55."
Also found a 12" cedar N12^oW 21 $\frac{1}{2}$ lks. with two apparent grown over blazes facing
corner as placed and described herein.

Corner re-established on line between section corners 40.128 ch. to
east and to west. Stream crossing is 20.11 ch. W, original field notes
indicate "stream 5 lks. e SW" 20.12 ch. W. of 1/4 corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

February 1, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68