

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 28 W


Dickinson COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 20-21-28-29

CORNER MONUMENT 1" Iron Pipe with 1/4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 12-29-62

WITNESSES TO CORNER..... NBT's: 1/4" Soft Maple (S29NBT) S 1/2° W 21 1/2 links



5" Hard Maple (S21NBT) N 28° E 55 links

9" Soft Maple (S20NBT) N 63° E 33 1/2 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by double proportionate measure from corners 1 mile East; 1 mile West; 1 mile South and Line Tree 10.91 chains North.

Found no evidence of original corner.

Found an iron pipe set 1.89 chains West of corner. This corner has been set at least 30 years, but believe it was placed in error.

SURVEYOR'S SEAL

SIGNED Billy B. Buckler DATE 8-22-63
REGISTERED LAND SURVEYOR
Billy B. Buckler