

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 28W


Dickinson COUNTY

DESCRIPTION OF CORNER Section Corner for Sections 25, 26, 35 and 36.

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 4-16-63

WITNESSES TO CORNER..... 3/4" Iron Pipe N. 68° E., 34½ Lks.



6" Black Cherry (N.B.T.) N. 41° W., 33 Lks.

5" Y. Pine (N.B.T.) S. 12° W., 38½ Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by double proportioned measurement bet. Section Corners 1 mile to E. and W. and 1 mile South and ½ mile North to ¼ Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckles DATE 10/7/63
REGISTERED LAND SURVEYOR