

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Dickinson

(County)	Located In:	Corner Code #
1. Public Land Survey	T 43N R 28W	A1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on December 01, 1994, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(A1) Corner common to Townships 43-44 N, Ranges 28-29W. Corner re-monumented at the location of an old Cedar post and original Cedar bearing tree in 1959 by Billy O. Buckler, RLS. He placed a 1" iron pipe with a 4" Brass cap at the corner and marked the following NBTs: 9" Tamarack N61E 124 links, 9" Cedar stub (dead) S17W 22 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A1) Recovered the 1959 monument, a 1" dia. iron pipe capped with a 4" dia. brass Michigan Dept. of Conservation cap, leaning. Plumbed and reset the monument in position and at record bearing and distance from the 1959 NBTs; now both dead and down. Marked four new bearing trees as described below. The original Cedar bearing tree noted in the 1959 record still exists at record bearing and distance from the corner - it is on the ground, but the markings are still very plain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A1) Found and straightened to an upright position a 1" iron pipe with 4" brass cap. Blazed and scribed the following witnesses:

- 5" Cedar N87W 82.5' "S36 NBT"
  - 9" Spruce S35E 18.4' "S6 NBT"
  - 4" Balsam S85E 18.5' "S6 NBT"
  - 5" Spruce N32W 62.0' "S36 NBT"
- Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 3-7-95  
Surveyor's Michigan License No. 33986