

72

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located in:

Corner Code #

1. Public Land Survey

T 43N R 28W I1

T 43N R 28W K1

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

Apr 21 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(I1) Corner common to Sections 2-3 T43N-R28W and Sections 34-35 T44N-R28W. Feb. 3, 1972 record by A.O. Enger states "October 21, 1969, Corner established by proportionate measurement on line between original corners 1 mile east and 4 miles west. Corner monument 1" I.D. x 3/8" iron pipe with 4" aluminum cap. Witnesses to corner, Basswood 12 S83E 116 links, Balsam 13 S76 1/2W 114.5 links".
(K1) Corner common to Sections 1-2 T43N-R28W and Sections 35-36 T44N-R28W. Corner perpetuated in the original position by Dean C. DeLaHater in 1953: "This corner was pointed out to be by H.S. Peterson, District Forester, of Iron Mountain. Corner had been previously located by Wm. Johnson, County Road Engineer, for Dickinson County. Two original B.T.'s still in place, down, in good condition. Corner was placed and witnessed December 8, 1953. Corner monument 1" pipe with 4" brass cap. Witnesses to corner: 12" Cedar N25E 21 links, 12" Cedar S78W 28 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I1) Recovered the 1969 monument as described and in good condition. Determined that the 1969 Enger survey was erroneous as the result of a measurement error made between E1 and K1. I rejected the monument as representing the position of the corner and I reestablished the corner by single proportionate measurement to the original record between section corners 5286.80' East and 10573.60' West, from which the 1969 monument was found Westerly 20.6'. I removed the 1969 monument and, at the position for the corner, I placed a 1" I.D. x 3/8" iron pipe capped with a yellow plastic cap stamped "MICH DNR PS 33986". Corner placed and witnessed by D. Lampela and B. Wheeler, Baraga District Office.

(K1) Recovered the 1953 monument as described, a 1" ID iron pipe capped with a 4" brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1953 Cedar bearing trees, both in good condition with blazes overgrown. The blaze on the Cedar NE was opened up to reveal the 1953 scribing. Left the monument in place and marked two new accessories as described below. Corner recovered and remitted by D. Lampela and B. Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I1) Set 1" iron pipe with plastic cap stamped "MICH DNR PS 33986". Blazed and scribed the following:
8" Balsam N01E 17.2' "S35 NBT"
11" Spruce S89E 53.9' "S2 NBT"
10" Sugar S62W 17.9' "S3 NBT"
6" Balsam S86W 68.1' "S3 NBT"
1969 NBT 20" Basswood S80E 56.8'. Pipe is set so that the top is 0.2' below ground level in south track of 2-track. Bearings are magnetic.

(K1) Found 1" pipe with 4" brass cap. Blazed and scribed the following:
9" Cedar N52W 5.3' "S35 NBT"
6" Cedar S17E 24.4' "S1 NBT"
The 1953 trees:
12" Cedar N28E 14.0' with opened blaze
13" Cedar S81W 18.5' blazes overgrown
Bearings are magnetic. Placed a squared cedar post adjacent.



Signed by

Stephan J. Szyszkoski

Date

6/25/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division