

74

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson	Located in:	Corner Code #
(County)		
1. Public Land Survey	T 43N R 28W	J1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Apr 15 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	19	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J1) Quarter corner common to Section 2 T43N-R28W and Section 35 T44N-R28W. January 31, 1972 record by A.O. Enger states "October 21, 1969: Corner reestablished 40.00 ch. west of original section corner 1,2,35, and 36, T43-44N, R28W on line between that corner and original township corner T43-44N, R28-29W. Corner monument 1" I.D.x36" iron pipe with 4" aluminum cap. Witnesses to corner: 8. Spruce 4 S80E 22 links, 8. Spruce 6 S74W 10 links, 8. Spruce 5 N35W 15 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J1) Recovered the 1969 monument as described and in good condition. Determined that the 1969 Enger survey was erroneous as the result of a measurment error made between E1 and K1. I rejected the monument as representing the position of the corner and I reestablished the corner by single proportionate measurement to the original record between Section corners 2643.40' West and 2643.39' East, from which the 1969 monument was found easterly 5.3 feet. I removed the 1969 monument and, at the position for the corner, placed a 1" I.D.x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J1) 1" iron pipe with 4" MDNR cap.

Blazed and scribed the following:

6" 8. Spruce S75W 17.5' "1/4S NBT"
6" Tamarack N47E 22.6' "1/4S NBT"
5" Tamarack N82E 21.6' "1/4S NBT"
5" 8. Spruce S82E 20.0' "1/4S NBT"
6" 8. Spruce S43W 1.4' "1/4S NBT"

Placed a squared spruce post adjacent.

Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

6/25/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division