

75

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey

T 43N R 28W F1

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Apr 16 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5				4		3		2		1	
3													
4	7	8				9		10		11		12	
5													
6	10	11				12		13		14		15	
7													
8	19	20				21		22		23		24	
9													
10	30	29				28		27		26		25	
11													
12	31	32				33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
(F1) Quarter corner common to Section 4, T43N-R28W and Section 33, T43N-R28W. Jan. 27, 1972 record by A.O. Enger states "October 16, 1969: Corner reestablished by proportionate measurement between reestablished section corners 40.00 ch. to east and to west. Corner monument 1" I.D. x 3/8" iron pipe with 4" aluminum cap. White Spruce 11 N14 1/2E 103.5 links, Balsam 14 N62 1/2W 100 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F1) Recovered the 1969 monument as described and in good condition. Determined that the 1969 Enger survey was erroneous as the result of a measurement error made between E1 and K1. I rejected the monument as representing the position of the corner and I reestablished the corner by single proportionate measurement to the original record between reestablished section corners 2643.40' east and west, from which the 1969 monument was found Westerly, 5.0'. I removed the 1969 monument and, at the position for the corner, placed a 1" I.D. x 3/8" iron pipe capped with a yellow plastic cap stamped "MICH DNR PS 33986". Corner placed and witnessed by B. Wheeler and O. Laapela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F1) Set 1" pipe with plastic cap stamped "MICH DNR PS 33986". Blazed and scribed the following:
10" Maple N29W 61.4' "1/4S NBT"
12" Maple N75E 43.7' "1/4S NBT"
8" Balsam S37E 37.3' "1/4S NBT"
6" Balsam S35W 28.3' "1/4S NBT"
Placed a squared maple post adjacent.
Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

6/25/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division