

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson
(County)

Located in: _____ Corner Code #/ _____

1. Public Land Survey T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S 21 T 43W R 28W 10
In Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Stephen J. Szyzowski, in a field survey on November 05, 1992, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

A. Description of original monument and accessories and/or subsequent restoration:

(10) Corner previously recorded by Billy D. Buchler, RLS in 1963 as monumented by a 1" pipe with a 4" aluminum cap. 1963 BTs are: 10" Jack pine S54N 03 links, 9" Jack pine N12W 40.5 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10) Found monument as recorded at record bearing and distance from the NW Jack pine BT, now a 12" tree with blazes overgrown. The other Jack pine BT was not recovered. Rescribed the 1963 BT and marked two new BTs as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Found a 1" pipe with a 4" aluminum Mich. Dept. of Conservation cap.
12" J. pine N12W 26.7' mrd "1/16s BT"
3" maple S03E S.0' mrd "1/16s BT"
6" W. Pine N65E 37.4' mrd "1/16s BT"
placed a 3" squared J. pine post S41W 0.7'.

Signed by Stephen J. Szyzowski Date 3-23-93
Surveyor's Michigan License No. 33986