

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 & 44 NR. 29 W.

Dickinson

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 5, 6, 31, 32

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 6" Tamarack S 26° W 37 links

8" Cedar S 88° E 61 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from one Tamarack B.T., poor condition (down). Positive identification, Scribe marks in overgrowth very plain. Two Tamarack stp. bottoms in proper position.

Corner found by Forestry Division Survey Crew while making a partail re-survey in this Township.

Section Corner lies 55 links East of 79.98 ch. marker from North.

Corner placed and witnessed April 18, 1956.

SURVEYORS SEAL

SIGNED

Billy E. Bucsis
REGISTERED LAND SURVEYOR

DATE 5/14/56