

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ⁴³ NR 29 W

Dickinson

COUNTY

DESCRIPTION OF CORNER Section corner common to sections 20, 21, 28 and 29
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap
WITNESSES TO CORNER Cedar 12" N 78 E 23 1/2 links, marked S 21 NBT
Cedar 14" S 4 E 21 1/2 links, marked S 28 NBT
Cedar 10" N 78 W 38 links, marked S 20 NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one original cedar bearing tree in fair condition, down, with scribe marks plain on description face. NE face rotted out. Found two wood stakes in place.

Corner was found while cruising timber in this area.

Corner was placed and witnessed on 23 April 1958.

SURVEYORS SEAL

Henry S. Peterson
SIGNED Henry S. Peterson DATE 4/23/58
REGISTERED LAND SURVEYOR