

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 NR. 29 W.

Dickinson

COUNTY

DESCRIPTION OF CORNER 1/4 corner between section 22 and 23

DESCRIPTION OF CORNER MONUMENT 1 1/2" X 5" galvanized iron pipe

WITNESSES TO CORNER Cedar 6" S 32 W Marked 1/4 S NBT, 15 links

Cedar 8" N 77 W Marked 1/4 S NBT, 32 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one original tamarack bearing tree in fair condition. Stump in place with BT scribes plain. Old rotten spruce stump in place for other bearing tree (original). Old squared cedar tree near corner, down.

Corner found while cruising timber in this area with Norman J. Karsten.

Corner was placed and witnessed on 20 May 1958 with Frank J. Bray.

SURVEYORS SEAL

Henry S. Peterson

Henry S. Peterson

SIGNED

REGISTERED LAND SURVEYOR

5/20/58
DATE